

PROJECT ADDRESS		SPRINGHILL SUITES MARRIOTT							Rev 0	
Date of submit	3/13/2020				KEY QUANTITIES					
Date of plans	5/31/2018				8" CMU	867	SF			
Scope	MASONRY	: Masonry Veneer Raincloud-Craft Warehouse Brick			8845	SF				
MASONRY	#REF!									
SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WAS TE	QTY. W/ WASTE	UNIT	REFERENC E UNIT COST	REFERENCE TOTAL COST
04 00 MASONRY										
BLOCK MASONRY										
TRASH ENCLOSURE										
8" CMU WALL										
1	A-1.13	A-1.13		8" Thick CMU wall Horizontal Reinforcement: Joint Reinforcement @ 16" O.C	392	10%	431	SF		\$ -
2	A-1.13	A-1.13		Bond Beam (2) #5 Continuous Bar	49	10%	54	LF		\$ -
Scaffolding										
3	A-1.13	A-1.13		Half height Scaffolding	49	10%	54	LF		\$ -
					SUB TOTAL					\$ -
PATIO AREA										
8" CMU WALL										
4	A-1.11	A-1.11		8" Thick CMU wall Horizontal Reinforcement: Joint Reinforcement @ 16" O.C Vertical reinforcement: #5 @ 24" O.C	213	10%	234	SF	\$ -	\$ -
5	A-1.11	A-1.11		Bond Beam (2) #5 Continuous Bar	50	10%	55	LF	\$ -	\$ -
6	A-1.11	A-1.11		1'-0" Wide Stone Cap @ Patio Area	50	10%	55	LF		\$ -
8" CMU WALL										
7	A-1.11	A-1.11		8" Thick CMU wall Horizontal Reinforcement: Joint Reinforcement @ 16" O.C Vertical reinforcement: #5 @ 32" O.C	184	10%	202	SF	\$ -	\$ -
8	A-1.11	A-1.11		Bond Beam (2) #5 Continuous Bar	60	10%	66	LF	\$ -	\$ -
					SUB TOTAL					\$ -
STONE CAP										
PATIO AREA										
9	A-1.11	A-1.11		1'-0" Wide Stone Cap @ Patio Area on 8" CMU Wall	50	10%	55	LF		\$ -
					SUB TOTAL					\$ -
VEENER @ FIRE PIT										
BRICK VEENER @ FIRE PIT										
10	A-1.14	A-1.14		Brick Veneer @ Fire Pit	213	10%	234	SF		\$ -
11	A-1.14	A-1.14		Pre Fab Top with Slate Tile (01 Each)	17	10%	18	SF		\$ -
					SUB TOTAL					\$ -

PROJECT		SPRINGHILL SUITES MARRIOTT								Rev 0												
ADDRESS																						
Date of submit	3/13/2020	<table border="1"> <thead> <tr> <th colspan="4">KEY QUANTITIES</th> </tr> <tr> <td>8" CMU</td> <td>867</td> <td>SF</td> <td></td> </tr> <tr> <td>Masonry Veneer Raincloud-Craft Warehouse Brick</td> <td>8845</td> <td>SF</td> <td></td> </tr> </thead> </table>									KEY QUANTITIES				8" CMU	867	SF		Masonry Veneer Raincloud-Craft Warehouse Brick	8845	SF	
KEY QUANTITIES																						
8" CMU	867	SF																				
Masonry Veneer Raincloud-Craft Warehouse Brick	8845	SF																				
Date of plans	5/31/2018																					
Scope	MASONRY																					
MASONRY	#REF!																					
SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WAS TE	QTY. W/ WASTE	UNIT	REFERENC E UNIT COST	REFERENCE TOTAL COST												
				CRAFT VENEER MASONRY																		
				PATIO AREA																		
12	A-1.11	A-1.11		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick	426	10%	469	SF		\$ -												
13	A-1.11	A-1.11		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick	420	10%	462	SF	\$ -	\$ -												
14	A-1.13	A-1.13		Scaffolding	420	10%	462	SF		\$ -												
SUB TOTAL										\$ -												
				PORTE COCHERE																		
15	A-1.12	A-1.12		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath with Scratch Coat Over/ Weather Resistant Barrier	395	10%	435	SF		\$ -												
16	A-1.12			Scaffolding	395	10%	435	SF	\$ -	\$ -												
SUB TOTAL										\$ -												
				SOUTH ELEVATION																		
17	A-2.01	3/A5.01		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath with Scratch Coat Over/ Weather Resistant Barrier	226	10%	249	SF	\$ -	\$ -												
18	A-1.12			Scaffolding	302	10%	332	SF	\$ -	\$ -												
SUB TOTAL										\$ -												
				EAST ELEVATION																		
19	A-2.01	2/A-7.04		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath w/ Brown Coat O/Laticrete mortar O/ Wire Mesh & Brown Coat over/ 1" Rigid Insulation w/ Weather Resistant Barrier	3,699	10%	4,069	SF		\$ -												
20	A-1.12			Scaffolding	4,111	10%	4,523	SF	\$ -	\$ -												
SUB TOTAL										\$ -												
				NORTH ELEVATION																		
21	A-2.01			ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath w/ Brown Coat O/Laticrete mortar O/ Wire Mesh & Brown Coat over/ 1" Rigid Insulation w/ Weather Resistant Barrier	651	10%	716	SF	\$ -	\$ -												
22	A-1.12			Scaffolding	891	10%	980	SF	\$ -	\$ -												
SUB TOTAL										\$ -												

PROJECT		SPRINGHILL SUITES MARRIOTT								Rev 0												
ADDRESS																						
Date of submit	3/13/2020	<table border="1"> <thead> <tr> <th colspan="4">KEY QUANTITIES</th> </tr> </thead> <tbody> <tr> <td>8" CMU</td> <td>867</td> <td>SF</td> <td></td> </tr> <tr> <td>Masonry Veneer Raincloud-Craft Warehouse Brick</td> <td>8845</td> <td>SF</td> <td></td> </tr> </tbody> </table>									KEY QUANTITIES				8" CMU	867	SF		Masonry Veneer Raincloud-Craft Warehouse Brick	8845	SF	
KEY QUANTITIES																						
8" CMU	867	SF																				
Masonry Veneer Raincloud-Craft Warehouse Brick	8845	SF																				
Date of plans	5/31/2018																					
Scope	MASONRY	Masonry Veneer Raincloud-Craft Warehouse Brick																				
MASONRY	#REF!																					
SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WAS TE	QTY. W/ WASTE	UNIT	REFERENC E UNIT COST	REFERENCE TOTAL COST												
WEST ELEVATION																						
23	A-2.01	1/A-5.02, 3/A5.11		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath w/ Brown Coat O/Laticrete mortar O/ Wire Mesh & Brown Coat over/ 1" Rigid Insulation w/ Weather Resistant Barrier	2,232	10%	2,455	SF	\$ -	\$ -												
24	A-2.01			Scaffolding	4,038	10%	4,442	SF	\$ -	\$ -												
SUB TOTAL										\$ -												
METAL COPPING																						
25	A-1.13	A-1.13		Metal Copping @ Trash Enclouser	49	10%	54	LF		\$ -												
26	A-1.11	A-1.11		Metal Copping @ Patio area	15	10%	17	LF	\$ -	\$ -												
27	A-2.01			Metal Copping @ East Elevation	40	10%	44	LF	\$ -	\$ -												
28	A-2.01			Metal Copping @ North Elevation	44	10%	48	LF	\$ -	\$ -												
29	A-2.01			Metal Copping @ West Elevation	150	10%	165	LF	\$ -	\$ -												